



## **BEFORE YOU TOW CHECKLIST**

### **INSIDE VAN:**

- Doors and cupboards closed and latched - give them a tug to check
- Table in travelling position
- Hatches are closed and secure
- Windows closed and latched
- Blinds and screens are secured in the open position
- TV secure
- TV antenna is wound down
- Stove lid is closed
- Fridge doors latched
- Fridge switched from gas to electricity, if your fridge isn't automatic
- Ensuite door is latched in open position
- Shower screen door is latched closed
- Shower head is secure or resting on ground - (Can be laid on a folded towel)
- Slider between toilet pan and cassette is in the closed position
- Check for loose items on benches etc.
- Water pump is turned off
- Any non essential electrics are switched off

## OUTSIDE VAN:

- Power leads and hoses away
- Stabilizer legs raised and secure
- All hatches are closed and latched
- Windows are closed and secured
- Antenna down
- Door locked
- Step is in travel position and secure
- Gas cylinders off
- Toolboxes and Generator box locked
- Drop down picnic table is secure
- All other external hatches are closed
- All lights checked and functioning correctly

## TOW VEHICLE:

- Tyres are inflated
- Lights are working
- Indicators are working
- Any items on roof rack are secured firmly
- Canopy windows are closed and locked

## TOW COUPLING:

- Is the coupling secure to the vehicle
- Safety chains secure, crossed and short enough to eliminate them dragging on the road, long enough to enable complete articulation from the hitch
- Trailer lights plugged in and checked that all lights work
- Anderson lead plugged in
- Trailer breakaway attached
- Jockey wheel raised, secured or stored